

Addendum Number 2

September 1, 2021

Cottonwood Ranch Recapture Well Network
Bid #1 Well Drilling, Pump Installation, and Electrical Supply
Bid #2 Pipeline and Outfall Structures

Notice to Prospective Bidders: this Addendum applies to both sets of bid documents (Bid #1 Well Drilling and Pump Installation and Bid #2 Pipeline and Outfall Structure). The addendum includes the clarifications/modifications included below.

The items in the bid documents are clarified/modified as follows:

1. The backflow prevention device which is furnished as part of the surface facilities in Bid #2 must meet requirements and intent of NEDHHS Title 178, Chapter 12. Surface facilities must all be rated for 150 psi.
2. Surface facility and pipeline fittings must be rated to a minimum 150 psi. Pipelines shall be tested according to the methods specified in AWWA Standard C605, however the test pressure shall be 90 psi, not 150 psi as specified by AWWA Standard C605.
3. The requirement for 10 pipe diameters describes the length of the spool upstream of the flow meter, and it must not include other "surface facilities".
4. To clarify D.3. in Bid #2 Pipeline and Outfall Structure, the NRD will supply the flow meters needed in the surface facilities, which will be installed by the contractor.
5. The SWPPP and stormwater permit will only be necessary for the pipeline work, not the well drilling and installation work.